

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- - (prior to '67) ✓

245 North Water  
Wichita, KS 67202

Operator's Full Name Chapman Exploration, Inc.

Complete Address 404 Cities Service Bldg., Tulsa. Oklahoma 74119

Lease Name Strobel Well No. 3

Location SE NW SW Sec. 33 Twp. 21S Rge. 14 (~~XXXX~~) (West)

County Stafford Total Depth 4088'

Abandoned Oil Well  Gas Well  Input Well  SWD Well XX D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour: 11:30 AM Day: 9 Month: 1 Year: 19 80

The above well was plugged as follows:

- Squeezed thru 8 5/8" surface casing, 5 1/2" casing, and 2 7/8" tubing with 1 sx hulls, and 300 sx cement.
- No casing recovery.
- 3884' of 2 7/8" tubing set with packer.
- 3901' of 5 1/2" casing cemented with 125 sx cement.
- 276' of 8 5/8" surface casing cement circ.

This well was used as a salt water disposal well.

This well had bad casing and the Dakota was flowing.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 1-13-81

INV. NO. 3899-W

Signed: Drew Rankin  
Conservation Division Agent

RECEIVED  
COMMISSION  
JAN 13 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
1-13-1981