

State of Kansas



15.185.20649.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

New Address
245 North Water
Wichita, Kansas 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1976

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

4-21-1976

Dear Sir:

Mr. Curtis of Duke Drlg Co has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Inland Oil & Gas Co

Complete Address: 5512 Plaza Lane Wichita, KS

Lease Name: Boyd Well No. 1

Location: SE/SE/SW Sec. 11 Twp. 21s Rge. 11 (E)(W) W

County: Stafford Total Depth 3645 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

411 ft 8 5/8 surface cemented with 250 sacks. Pump plug
50 sacks cement to 600 ft. 2nd plug at 350 ft, 25 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole, 2 in water well.

Pumped by Allied Cementing Great Bend, KS

Very truly yours,

[Signature]
Conservation Division Agent