



15-185-10113-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. W. F. Banks of Isern Drilling Company has this date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: H. L. Herbel

Complete Address: Box 327, Chase, Kansas

Lease Name: Anschutz Well No. # 1

Location: C S/2 S/2 SE Sec. 10 Twp. 21 Rge. 14 (E)(W) W

County Stafford Total Depth 3726' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Banks was instructed to plug the well as follows:

310' of 8 5/8" surface pipe, cement circulated with 225 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent