



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202
December 6, 1980

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Roy Lindsay of Merkle Drilling Co.

date requested permission to plug the following described well:

Operator's Full Name: Graves Drilling Company, Inc.

Complete Address: 910 Union Center, Wichita, Kansas

Lease Name: Krampe Well No. 2

Location: SW 1/4 SW Sec. 15 Twp. 21 Rge. 14 (W)

County: Stafford Total Depth: 3770'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Lindsay was instructed to plug the well as follows:

8 5/8" - 464' - 325 sacks 60/40 Pozmin 2% gal 3% cal. chl. Fill hole with mud.
Pump 50 sacks cement through drill pipe at 475'. Fill hole
with mud to 46'. Push plug and 2 sack hulls to 40'
and cap hole with 10 sacks cement. Cement rat hole
with 5 sacks. Cement mousehole with 5 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent

STATE CORPORATION COMMISSION
DEC 11 1980
has this
CONSERVATION DIVISION
Wichita, Kansas