



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

8-4-82

VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-185-21654

Dear Sir:

Mr. Larry Henderson of Rainey, Wilkinson ^{Big 4} has this date requested permission to plug the following described well:

Operator's Full Name: Penguin Petro, Inc. #5234

Complete Address: 515 4th Financial Ctr. Wichita Kansas 67202

Lease Name: Krump Well No. 1

Location: SE-SE-SE Sec. 33 Twp. 21 Rge. 14 (E) (W)

County: Stafford Total Depth: 3820'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Henderson was instructed to plug the well as follows:

They set 288' of 8 5/8" surface casing cemented with 236 lbs of 60/40 2 3/4 gal 3 1/2 cc. The anhydrite was at 853'. 1st plug at 850' with 50 lbs of cement. 2nd plug at 335' with 40 lbs of cement. 3rd plug 40' to 0' on solid bridge with 10 lbs of cement. Then circulate 10 lbs of cement in rat hole + 5 lbs of cement in water well.

Very truly yours,

Paul A. Luthie
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1982
CONSERVATION DIVISION
Wichita, Kansas