

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.113.02129.0001

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bailey of Union Texas Pet. has this

date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum

Complete Address: Box 562 Great Bend, Kansas

Lease Name: Goossen Well No. # 4

Location: NE NE NE Sec. 12 Twp. 21 Rge. 1 (E) (W)


County McPherson Total Depth 3530' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bailey was instructed to plug the well as follows:

8 5/8"-221'-Circulated w/cement. 5 1/8"-3449'-Cemented. Sand hole to 3040'.
5 Sax.cement 3040' to 3000'. Mud 3000' to 200'. Bridge 200' to 190'.
25 Sax.cement 190' to 115'. Mud 115' to 40'. Bridge 40' to 30'.
10 Sax.cement 30' to 0.

Very truly yours,


Conservation Division Agent