

State of Kansas



15.113.02332.0002

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 1 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bailey of Union Texas Pet. has this

date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum

Complete Address: Box 526 Great Bend, Kansas

Lease Name: Klassen Well No. # 2

Location: NE NW SE Sec. 12 Twp. 21 Rge. 1 (E) (W)

County McPherson Total Depth 3408' Oil Well X

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Bailey was instructed to plug the well as follows:


8 5/8"-225'-Circulated w/cement. 4 1/2"-3402'-Cemented. Sand hole to 3390'.

3 Sax.cement 3390' to 3350'. Mud 3350' to 220'. Bridge 220' to 210'.

25 Sax.cement 210' to 135'. Mud 135' to 40'. Bridge 40' to 30'.

10 Sax.cement 30' to 0.

Very truly yours,

  
Conservation Division Agent