



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1965

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ryan of Pan American Pet. Corp. has this

date requested permission to plug the following described well:

Mr. Ryan guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corp.

Complete Address: Box 432 Liberal, Kansas

Lease Name: J.M. Mc Nellis Well No. # 1

Location: C SW SW Sec. 27 Twp. 21S Rge. 35 (E) (W)

County Kearney Total Depth 4650' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ryan was instructed to plug the well as follows:

8 5/8"-1255' Circulated w/cement.

Mud 4650' to 1660' Johnson testing tool lost at 1660'

Spotted 50 Sax. cement 1660' to 1510' Mud 1510' to 700'

Spotted 35 Sax. cement 700' to 600' Mud 600' to 45'

Plug, 15 Sax. cement 45' to 0

Very truly yours,

Richard Scott
Conservation Division Agent