

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 009-23,761-00-00

LEASE NAME Bitter

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 5 TWP. 16 RGE. 13 (E) or (W)

COUNTY Barton

Date Well Completed 12-04-84

Plugging Commenced 03-05-86

Plugging Completed 03-10-86

LEASE OPERATOR Boger Brothers Drilling

ADDRESS Box 723, Great Bend, Kansas 67530

PHONE# (316) 792-8151 OPERATORS LICENSE NO. 9421

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3336 Bottom 3342 T.D. 3440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	392	10 13/4"	392	0
Production		0	3417	7"	3417	1680'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
03-05-86 Sanded 7" casing to 3270'. Dumped 7 sacks cement on top. Shot casing at 2090', wouldn't come, shot again at 1680', started pulling. 03-06-86 Pulled 1680' of 7" casing. 03-10-86 Halliburton pumped 5 sacks of hulls and 250 sacks of cement. Maximum pressure 600 lbs. Shut in pressure 400 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

STATE OF Kansas COUNTY OF Barton, ss.

Boger Brothers Drilling

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marvin R. Boy

(Address) P.O. Box 723, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 86

Carie Karlin
Notary Public

My Commission Expires: 2/20/86



MAR 17 1986

CONSERVATION DIVISION
Wichita, Kansas
Revised 08-84