


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 32 Twp. 21S Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Bennett & Gould
Lease Name Graber Well No. 1
Office Address 5806 No. Broadway, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-8-58 19
Application for plugging filed 1-8-58 19
Application for plugging approved 1-8-58 19
Plugging commenced 1-8-58 19
Plugging completed 1-8-58 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3704 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing		2426		8 5/8"	202'	None
Miss. Lime		3131				
Kinderhook		3454				
Misner		3524				
Hunton Dolomite		3534				
Maquoketa Shale		3558				
Viola Lime		3647				
Simpson Dolomite		3676				
Simpson Sand		3682				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with mud from 3704' to 195'; plug set at 195'; 20 sacks cement from 195' to 80'; mud from 80' to 25'; 25 sacks cement from 25' to 0'.

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1958
CONSERVATION DIVISION
Wichita 7-14-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SeRoBee Drilling Co., Inc.
Address 422 Union National Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Paul S. Septer (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul S. Septer
422 Union National Bldg., Wichita, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 19 58
Marilyn Garat Busch
Notary Public.

My commission expires Nov. 8, 1960

PLUGGING
FILE SEC. 32, T. 21, R. 24
PAGE 76 LINE 15

GRABER #1

COMPANY: Bennett & Gould LOCATION: SW SW SW, Sec. 32-21S-2W,
 CONTRACTOR: SeRoBee Drlg. Co., Inc. McPherson County, Kansas
 COMMENCED: 12-23-57 ELEVATION: 1470 RB
 COMPLETED: 1-8-58 CASING: 202' of 8 5/8", cemented
 TOTAL DEPTH: 3704' with 200 sacks.

0	30	Shale
30	150	Sand
150	182	Shale & lime
182	202	Shale & lime
202	467	Shale
467	650	Shale & shells
650	700	Lime
700	775	Lime & shale
775	900	Shale & lime
900	1100	Lime & shale
1100	1250	Lime & shale
1250	1486	Shale & lime streaks
1486	1686	Shale & shells
1686	1796	Shale & shells
1796	1895	Shale & lime
1895	1970	Lime & shale
1970	2100	Lime & shale
2100	2188	Lime & shale
2188	2398	Shale & shells
2398	2440	Shale & shells
2440	2506	Lime
2506	2568	Lime
2568	2655	Lime & shale
2655	2695	Lime
2695	2710	Lime & shale
2710	2740	Lime & shale
2740	2780	Sandy shale
2780	2805	Shale & lime
2805	2877	Lime & shale
2877	2937	Shale & lime
2937	3014	Shale & lime
3014	3120	Shale & lime
3120	3131	Shale
3131	3148	Mississippi Lime
3148	3193	Mississippi Lime
3193	3224	Mississippi Lime
3224	3264	Mississippi Lime
3264	3319	Mississippi Lime
3319	3410	Mississippi Lime
3410	3429	Lime-Mississippi
3429	3455	Mississippi Lime
3455	3528	Shale & lime
3528	3540	Lime
3540	3623	Lime & shale
3623	3647	Shale
3647	3676	Viola Lime
3676	3704	Simpson Sand
3704		Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 14 1958
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 32 T 21 R 2W
 BOOK PAGE 76 LINE 15

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Graber #1, located in the SW SW SW, Sec. 32-21S-2W, McPherson County, Kansas.

SEROBEE DRILLING CO., INC.

Paul S. Septer
 Paul S. Septer

Subscribed and sworn to before me this 9th day of January, 1958.

Marilyn Garst Busch
 Notary Public

Commission Expires November 8, 1960.