


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 33 Twp. 21S Rge. (X) 2 (W)

Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner John C. Graves, et al
Lease Name Stucky Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 16, 19 66
Application for plugging filed March 16, 19 66
Application for plugging approved March 16, 19 66
Plugging commenced March 16, 19 66
Plugging completed March 16, 19 66
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Hugh Scott, McPherson, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 230 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) John C. Graves
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of March 29, 19 66

Betty Brandt
Notary Public.

My commission expires April 30, 1967

R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves, et al DRILLING COMMENCED: March 10, 1966
 412 Union Center
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 16, 1966
 412 Union Center
 Wichita, Kansas

CASING RECORD: 12 Jts. 242' 8-5/8" LOCATION: Stucky No. 1
 cemented with 185 sacks C SE NE
 Section 33-21S-2W
 McPherson County, Kansas

0 - 35	Sod, clay & shale
35 - 100	Sand
100 - 242	Shale & clay
242 - 376	Shale & lime
376 - 940	Lime & shale
940 - 1770	Shale & lime
1770 - 1963	Lime & shale
1963 - 2098	Lime
2098 - 2212	Lime & shale
2212 - 2370	Shale, sand & lime streaks
2370 - 2795	Lime
2795 - 3106	Shale & lime
3106 - 3382	Lime
3382 - 3542	Lime & shale
3542 - 3590	Lime
3590 - 3605	Sand
3605	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 30 1966
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
 President

STATE OF KANSAS)
) SS:
 BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 29th of March, 1966.

Betty Brandt
 Betty Brandt Notary Public

My commission expires:
 April 30, 1967