

API NUMBER 15.185.0185 4.0000

LEASE NAME Asher

WELL NUMBER #2

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 4 TWP. 21 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed 12-16-55

Plugging Commenced 11-26-88

Plugging Completed 11-29-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Woodman Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE# (316) 792-1934 OPERATORS LICENSE NO. 6588

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 21, 1988 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached? With application

Producing Formation                      Depth to Top                      Bottom                      T.D. 3599'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	830'	None
				5-1/2"	3598 1/2'	2864.76'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3245' and 5 sacks cement. Shot casing at 3000' and 2800'. Pulled 91 joints of 5-1/2" casing, B. J. Titan plugged well with 300# hulls, 10 sacks gel, 50 sacks 60/40 pozmix cement with 6% gel, 5 sacks gel, 100# hulls and 100 sacks cement. Maximum pressure was 800 psi and shut in 500 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 6 1988

SUBSCRIBED AND SWORN TO before me this 5th day of December, 19 88

Iona M. Leatherman  
 Notary Public

STATE NOTARY PUBLIC  
 IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Appt. Exp. 4-26-91

My Commission Expires: