

15.185.00178.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 4 Twp. 21 Rge. (E) 14(W)

Location as "NE/CNW/SW" or footage from lines Stafford, SE SW SW

Lease Owner Westgate-Greenland Oil Co & Harms & Knight Drlg

Lease Name Boyd B Well No. 1

Office Address 1009 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed February 2, 1953 19

Application for plugging filed (orally) Feb 2, 1953 19

Application for plugging approved Feb 4, 1953 (written) 19

Plugging commenced February 2, 1953 19

Plugging completed February 2, 1953 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. W. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	855	8 5/8"	853	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3665 to 300 feet
Set plug at 300 feet and ran 20 sacks cement to 240 feet
Filled with heavy mud from 240 to 35 feet
Set plug and ran 10 sacks cement from 35 to cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms and Knight Drilling Company

Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

G. E. Bitler (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler

1009 Central Building, Wichita Ks

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February

Esther [Signature] Notary Public.

My commission expires May 25, 1953.

24-2675-5 2-52-20M

PLUGGING
FILE SEC 4 T 21 R 14
BOOK PAGE 22 LINE 20

RECEIVED
FEB 14 1953
2-14-1953
CONSERVATION DIVISION
Wichita, Kansas

COMPANY: Westgate-Greenland Oil Company and
Harms-Knight Drilling Company

FARM: Boyd B 1 , SE SW SW 4-21S-14W
Stafford County, Kansas

CONTRACTOR: Harms-Knight Drilling Company

COMMENCED: January 20, 1953

COMPLETED: February 2, 1953

ELEVATION: 1927 DF

0	to	15	Clay
15	to	85	Sand
85	to	285	Shale and shells
285	to	370	Sand
370	to	560	Red bed
560	to	848	Red bed and shells
848	to	873	Anhydrite
873	to	1125	Red Bed and shale
1125	to	1230	Shale
1230	to	1290	Shale and shells
1290	to	1345	Shale and salt
1345	to	1515	Shale and shells
1515	to	1710	Shale and lime
1710	to	1780	Lime and sand
1780	to	2060	Lime
2060	to	2085	Lime and shale
2085	to	2145	Lime
2145	to	2815	Lime and shale
2815	to	2841	Shale
2841	to	2929	Lime
2929	to	3005	Lime and shale
3005	to	3212	Lime
3212	to	3303	Shale and lime
3303	to	3576	Lime
3576	to	3602	Lime, shale and sand
3602	to	3632	Shale and lime
3632	to	3665	Lime
		3665	T. D. (RB)

Set 853 feet of 8 5/8" Surface. Cemented with 450 sacks

TOPS: Anhydrite	848	Lansing	3314	Simpson	3582
Heebner	3202	Viola	3547	Arbuckle	3632
Brown Ls.	3303				

Drill Stem Tests:

3328-86, open 1 hour, wk blow for 23 min, rec. 20' mud,
BHP 246#.

3352-74, open 30 min, wk blow for 6 min, rec. 15' mud,
BHP 16#.

No Schlumberger run
DRY, PLUGGED AND ABANDONED

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of log of the Boyd B-1 SE SW SW Section 4-21S-14W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

Harold A. Burt
Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 13th day of February, 1953.

Esther Unsell
Esther Unsell, Notary Public

My Commission Expires May 25, 1953.

