

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Stafford County, Sec. 4 Twp. 21 Rge. 14 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SE SE SW

Lease Owner Inland Oil and Gas Corporation

Lease Name Boyd Well No. 1

Office Address 5512 Plaza Lane, Wichita, Kansas 67218

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 19 19 76

Application for plugging filed April 19 19 76

Application for plugging approved April 19 19 76


Plugging commenced April 19 19 76

Plugging completed April 19 19 76

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3645 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full heavy mud to 600' and 50 sacks cement thru drill pipe.
Mud to 350' w/25 sacks cement thru drill pipe.
Mud to 40' w/1/2 sack hulls plug & 10 sacks cement.
2 sacks cement in rat hole.
2 sacks in water well.

RECEIVED
CONSERVATION COMMISSION
APR 21 1976
CONSERVATION DIVISION
Wichita, Kansas
4-21-1976

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co.
Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON
Larry Curtis (employee of owner) or (XXXXXXXXXX) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April 19 76

My commission expires April 11, 1978
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: April 14, 1976
 DATE COMPLETED: April 19, 1976

Inland Oil and Gas Corporation
 "BOYD # 1"
 SE SE SW
 Sec 4-T21-RL4W
 Stafford County, Kansas

ELEVATION: 1942 K.B.

0 - 224' Sand
 224 - 415' Shale and Sand Streaks
 415 - 836' Red Bed
 836 - 860' Anhydrite
 860 - 3207' Shale and Lime
 3207 - 3211' Shale
 3211 - 3307' Shale and Lime
 3307 - 3317' Lime and Shale
 3317 - 3540' Lime
 3540 - 3516' Lime and Shale
 3516 - 3587' Chert
 3587 - 3613' Shale
 3613 - 3618' Sand
 3618 - 3639' Lime and Shale
 3639 - 3645' Dolomite
 3645' RTD

FORMATION TOPS

Anhydrite	836
Heebner	3207
Brown Lime	3307
Lensing	3317
Base K.G.	3540
Viola	3516
Simpson Shale	3587
Simpson Sand	3613
Arbuckle	3639
RTD	3645

SURFACE PIPE: Set used 28#
 pipe @ 414' w/250 sacks Common,
 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 20th day of April, 1976.

Clarity M. Hague
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED
 STATE OF KANSAS COMMISSIONER
 APR 21 1976
 CONSERVATION DIVISION
 (Wildlife, Fisheries)