

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Stafford County, Sec. 10 Twp. 21 Rge. 14 (E) ~~W~~ (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE  
Lease Owner ANSHUTZ Icer Addis  
Lease Name ANSHUTZ Well No. 2  
Office Address 5307 East Central, Wichita, Ks. 67208  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 23 1973  
Application for plugging filed " " 1973  
Application for plugging approved " " 1973  
Plugging commenced February 23 1973  
Plugging completed February 23 1973  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3705 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Squeezed 90 sacks 60/40 pozmix with 2% Gel down 8-5/8" surface pipe

2 sacks cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Kansas COUNTY OF Barton, ss.  
Leonard Williamson (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson  
Box 823 - Great Bend, Ks. 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of February, 19 73

My commission expires 4-11-1974  
Verethy M. Hoque Notary Public.

W E L L L O G

DATE COMMENCED: February 14, 1973  
 DATE COMPLETED: February 23, 1973

Icer Addis  
 ANSHUTZ #2  
 NW SW SE  
 Section 10-21-14w  
 Stafford County, Ks.

0 - 224' Clay & Sand  
 224 - 265' Shale  
 265 - 360' Clay & Sand Streaks  
 360 - 829' Red Bed  
 829 - 852' Anhydrite  
 852 - 1660' Shale  
 1660 - 1820' Shale & Lime streaks  
 1820 - 2878' Shale & Lime  
 2878 - 3238' Lime  
 3238 - 3242' Shale  
 3242 - 3262' Lime & Shale  
 3262 - 3283' Lime  
 3282 - 3353' Shale  
 3353 - 3364' Lime, Br.  
 3364 - 3601' Lime  
 3601 - 3619' Lime & Shale  
 3619 - 3651' Chert  
 3651 - 3658' Shale  
 3658 - 3661' Sand  
 3661 - 3698' Shale & Sand  
 3698 - 3705' Dolomite

ELEVATION: 1932 K.B.

FORMATION DATA

ANHYDRITE	829
TOPEKA	2878
HEEBNER	3238
TORONTO	3262
DOUGLAS	3283
BR. LIME	3353
KANSAS CITY	3364
BASE K.C.	3601
VIOLA	3619
SIMPSON SHALE	3651
SIMPSON SAND	3658
ARBUCKLE	3698
RTD	3705

SURFACE PIPE: Set used 8-5/8" 28# pipe with 215 sacks common at 265'.

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 27 1973  
 CONSERVATION DIVISION  
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS,  
 COUNTY OF BARTON SS

Leonard Williamson of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 26 day of February 1973.

My Comm. Expires:  
April 11, 1974.

*Christy M. Hague*  
 Notary Public