

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 10 Twp. 21S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE

Lease Owner Alpine Drilling Co., Inc.

Lease Name Anshutz Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed June May 16, 1969 19

Application for plugging filed " May 16, 1969 (by phone) 19

Application for plugging approved " May 16, 1969 (by phone) 19


Plugging commenced " May 16, 1969 19

Plugging completed " May 16, 1969 19

Reason for abandonment of well or producing formation Nonproductive in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. J. Warren

Producing formation Depth to top Bottom Total Depth of Well 3735 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	354 feet	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from total depth to 450 feet. Plug and 50 sacks cement at 450 feet. Heavy mud to 240 feet. Second plug at 240 feet with 25 sacks cement. Top plug at 40 feet with 1/2 sack hulls. 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert Jones,
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Jon T. Williams, Jr.
800 Bitting Bldg., Wichita, Kan.
(Address)

Subscribed and Sworn to before me this 19 day of June, 1969

Evelyn Wanko
Evelyn Wanko Notary Public.

My commission expires December 10, 1972



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ANSHUTZ #1
 C NE SE Section 10-21S-14W
 Stafford County, Kansas

Commenced: June 8, 1969
 Completed: June 16, 1969

OPERATOR - Alpine Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	200	Sand	
200	244	Shale	
244	348	Sand	Ran 17 joints of 8-5/8" surface casing, set @ 348' w/310 sacks cement.
348	565	Shale and shells	
565	817	Shale and red bed	
817	848	Anhydrite	
848	1212	Shale	
1212	1630	Shale and shells	
1630	1845	Lime and shale	
1845	1970	Lime	
1970	2173	Lime and shale	
2173	2500	Shale	
2500	3035	Shale and lime	
3035	3233	Lime	
3233	3360	Shale and lime	
3360	3735	Lime	
3735	TD		Dry and abandoned.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 20 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SE Section 10-21S-14W, Stafford County, Kansas, to the best of my knowledge and belief.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18 day of June, 1969, personally appeared E. E. HALL to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton

 Barbara J. Layton, Notary Public

