

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County, Sec. 10 Twp. 21S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines C-SE SE SW

Lease Owner Sunray Oil Corporation

Lease Name Gilmore Well No. 1

Office Address ~~KOKO~~ Box 195, Great Bend, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-28 19 52

Application for plugging filed 4-2 19 52

Application for plugging approved 4-3 19 52

Plugging commenced 4-30 19 52

Plugging completed 5-7 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 3721 Feet

Show depth and thickness of all water, oil and gas formations. PB 3666 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lsg-KC	Dry	3371	3555			
Simpson	Dry	3686	3702			
Arbuckle	Water	3714	3721	8-5/8"	845'	None
				5-1/2"	3715'	2977'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3666' to 3450' and ran 5 sax cement. Mudded hole from 3300' to 300', set 10' rock bridge and ran 20 sax of cement. Mudded hole to 10', set 10' rock bridge and ran 10 sax of cement. Plugging completed.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1952  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor West Supply Co.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
W. E. Westbrook, Jr. (employee of owner) or (operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr. Jr. Engineer

Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of May, 19 52

Martha Scott

Notary Public.

My commission expires April 19, 1956

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 10 T 21 R 14 W  
BOOK PAGE 19 LINE 19

Gilmore No. 1 Well

Sec. 10-21S-14W, Stafford County, Kansas

Drilled for: Sunray Oil Corporation

Drilled by: Mouser Drilling Company

Drilling Commenced: February 25, 1952  
 Drilling Completed: March 9, 1952

Casing Record:

8 5/8" 845' 2 1/4" 8 rd thd  
 5 1/2" 3715' O.D. 1 1/4" 8 rd thd

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5		
Sand	220		
Shale	280		
Sand	360		
Red Bed	415		
Red Bed & Shale	530		
Shale & Shells	837		
Anhydrite	846	- Reaming to 13 3/4" Hole	
Anhydrite	862		
Shale & Shells	1335		
Salt	1485		
Shale & Shells	1710		
Lime	1820		
Lime & Shale	2995		
Lime	3286		
Shale	3361		
Lime	3605		
Lime & Shale	3621		
Conglomerate	3626		
Chert	3645		
Chert & Shale	3664		
Shale	3686		
Simpson Sand	3692		
Shale	3714		
Arbuckle	3718		
Total Depth	3718		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 15 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

A. L. Mouser

Subscribed and sworn to before me this 17th day of March 1952.

Frances L. Helber  
 Notary Public

My Commission Expires:  
March 18 1954

PLUGGING  
 FILE SEC 10 T 21 R 14W  
 PAGE 24 LINE 19