


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 10 Twp. 21 Rge. 14 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE NE SW  
Lease Owner Raymond Oil Company, Inc.  
Lease Name GILMORE Well No. #1  
Office Address One Main Place Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 3-20 1981  
Application for plugging filed 3-20 1981  
Application for plugging approved 3-20 1981  
Plugging commenced 3-21 1981  
Plugging completed 3-21 1981  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation Depth to top Bottom Total Depth of Well 3705'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug: @520' w/40 sacks 50/50 pozmix thru drill pipe

Middle Plug: @275' w/30 sacks " " " " "

Top Plug: @40' w/solid bridge of  $\frac{1}{2}$  sack hulls & 10 sacks cement  
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Bill Draney (employee of owner) or  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney  
P.O. Box 823 Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of March, 1981

Maureen M. Hague  
Notary Public.

My commission expires 4-11-1982

RECEIVED  
STATE CORPORATION COMMISSION

MAR 25 1981

CONSERVATION DIVISION  
Wichita, Kansas

3-25-1981

15.185.21244.0000

DRILLERS' WELL LOG

DATE COMMENCED: March 12, 1981  
DATE COMPLETED: March 21, 1981

Raymond Oil Co., Inc.  
GILMORE #1  
SE NE SW  
Sec. 10, T21S, R14W  
Stafford County, Ks.

0	-	225'	Clay & Sand
225	-	283'	Shale
283	-	365'	Sand
365	-	833'	Shale & Red Bed
833	-	858'	Anhydrite
858	-	3018'	Shale & Lime
3018	-	3241'	Lime
3241	-	3245'	Shale
3245	-	3255'	Lime & Shale
3255	-	3274'	Lime
3274	-	3355'	Shale
3355	-	3366'	Lime & Shale
3366	-	3584'	Lime
3584	-	3610'	Lime, Shale
3610	-	3705'	Chert, Lime
		3705'	RTD

Elevation: 1935 K.B.

FORMATION DATA

Anhydrite	833'
Topeka	3018'
Heebner	3241'
Toronto	3255'
Douglas	3274'
Br. Lime	3355'
Lansing K.C.	3366'
Base K.C.	3584'
Viola Chert	3610'
RTD	3705'

Surface Pipe: Set 280' of  
8-5/8", new 20# pipe w/250  
sacks 50/50 pozmix, 2% gel,  
3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and  
statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 24 day of March 1981.

My Comm. Expires:

4-11-1982

Donna M. Blaque  
Notary Public

RECEIVED  
CONSERVATION DIVISION

MAR 25 1981

CONSERVATION DIVISION  
WICHITA, KANSAS