


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 10 Twp. 21 Rge. 11 (E) (W)
Location as "NE/CNWxSWx" or footage from lines SE SE/4 NW/4
Lease Owner Veeder Supply & Development Co.
Lease Name Rehm Well No. 1
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 28 19 55
Application for plugging filed July 28 19 55
Application for plugging approved July 28 19 55
Plugging commenced July 28 19 55
Plugging completed July 28 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner, Great Bend, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	830'	cemented w/400 sacks cement

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with heavy mud to 300', put in 1/3 sack hulls, plug and 20 sacks cement poured through D. P.; heavy mud to 35', 1/3 sack hulls, 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply & Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Leo C. Veeder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo C. Veeder
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 55

My commission expires July 11, 1956

Loles Lawson
Notary Public.

PLUGGING
FILE SEC. 10 T. 21 R. 14W
BOOK PAGE 132 LINE 9

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 X 1955
CONSERVATION DIVISION
Wichita, Kansas

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Stanolind Oil & Gas Company,

Drilled for Veeder Supply & Dev'l. Co. et al Farm Rehn No. 1 Depth 3730'

Contractor Veeder Supply & Development Co. Pipe 830' 8 5/8" csg. cemented w/100 sacks cement

Location Veeder Supply & Development Co. SE/4 NW/4 Sec. 10 Twp. 21 Range 14

Commenced 7-15-1955 Completed 7-28 County Stafford State Kansas

Sand and gravel	0	205	205
Shale	205	210	5
Shale and lime streaks	210	350	140
Red bed and shale	350	530	180
Red bed, shale and shells	530	812	282
Chalk and anhydrite	812	820	8
Anhydrite	820	855	35
Shale and shells	855	1650	795
Lime and shale	1650	1870	220
Lime broken	1870	1900	30
Lime and shale streaks	1900	1930	30
Lime	1930	2010	80
Lime and shale	2010	3125	1115
Lime	3125	3235	110
Lime and shale	3235	3360	125
Lime	3360	3610	250
Lime and chert	3610	3620	10
Lime, shale and chert	3620	3680	60
Lime and shale	3680	3710	30
Lime	3710	3730	20
T. D.	3730		
Dry and abandoned			

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Rehn #1 well located in Section 10-21-14, Stafford County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

BY Leo C. Veeder
 Leo C. Veeder

Subscribed and sworn to before me this 30th day of July, 1955.

Leo Lawson
 Notary Public

My commission expires July 11, 1956.

PLUGGING
 FILE SEC 10 T 21 R 14 W
 BOOK PAGE 139 LINE 9

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 3 X 1955
 CONSERVATION DIVISION
 Wichita, Kansas