


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 15 Twp. 21S Rge. 14 (X) W (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner Vickers Petroleum Co., Inc., & Jayhawk Drilg. Co., Inc.
Lease Name Anschutz Estate Well No. 1
Office Address 201 W-K-H Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 16 19 50
Application for plugging filed December 16 19 50
Application for plugging approved December 16 19 50
Plugging commenced December 16 19 50
Plugging completed December 22 19 50
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough, Great Bend, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	700'	
				5-1/2"	3725'	3292'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 4' Rock @ 3731'. Dump 6 sx cement to 3695'. Filled w/mud to 250'.
Set Rock Bridge, dump 15 sx cement. Filled w/mud to 40'. Set rock bridge
& dump 10 sx cement for cap.

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to The Vickers Petroleum Co., Inc.
Address 201 W-K-H Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little
201 W-K-H Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 1951

Allen P. Denton
Notary Public.

My commission expires August 13, 1953.

PLUGGING
FILE SEC 15 T 21 R 14
BOOK PAGE 51 LINE 30

THE VICKERS PETROLEUM CO., INC.
&
JAYHAWK DRILLING CO., INC.

Arschutz Estate well #1
SE SE NE Sec. 15-21S-14W
Stafford County, Kansas

Casing Record:
8-5/8" @ 700' w/325 sx
5-1/2" @ 3725' w/75 sx

Commenced: November 29, 1950
Completed: December 16, 1950

Elevation: 1929 R.B.
D & A

L O G

Surface	0-260
Sand Streaks	260-320
Red Bed, Shale & Shells	320-699
Red Bed	699-828
Anhydrite	828-852
Red Bed, Shale & Shells	852-1285
Shale & Shells	1285-1340
Shale & Salt	1340-1585
Shale & Lime	1585-1640
Lime & Shale	1640-1770
Broken Lime	1770-1900
Broken Lime & Sand	1900-1970
Lime & Sand	1970-2075
Lime & Shale	2075-2850
Lime	2850-3015
Lime & Shale	3015-3282
Shale	3282-3372
Lime & Shale	3372-3640
Cherty Conglomerate	3640-3645
Chert, White	3645-3677
Shale	3677-3704
Sand	3704-3708
Shale	3708-3724
Dolomite	3724-3735 T.D.

DST 3651-3683, open 15 min. Lt. blow
for 13 min. Rec. 5' mud.
DST 3725-3730, open 10 min. Lt. blow
4 min. Rec. 10' oil cut mud.
DST 3725-3735, open 30 min. Good blow.
Rec. 270' muddy oil, BHP 1000#.
Drilled plug and swab 6 B.F.P.H. Est. 90% wat.
F.U. 14 hrs. 2200' fluid (300' oil & 1900' wat.)
Swabbed water. D & A.

Tops:
Heebner
Brown Lime
Conglomerate
Viola
Simpson
Arbuckle

RECEIVED
3258 CONSERVATION COMMISSION
3372
3640 JAN 12 1951
3645 CONSERVATION DIVISION
3677 Wichita, Kansas
3724

I hereby certify that this log is true and correct to the best of my
knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By W.P. Summers

Sworn and subscribed to before me
this 18th day of December, 1950.

Allen P. Denton
Notary Public

My commission expires Aug. 13, 1953

PLUGGING
FILE SEC. 15 T. 21 R. 14
BOOK PAGE 51 LINE 30