


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
830 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 15 Twp. 21 Rge. 14 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C.W. $\frac{1}{2}$ NW NE
Lease Owner Anschutz Drilling Co., Inc.
Lease Name Anshutz Well No. 1
Office Address 1307 $\frac{1}{2}$ Main St. Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-20 19.52
Application for plugging filed 4-11 19.52
Application for plugging approved 4-14 19.52
Plugging commenced 4-24 19.52
Plugging completed 4-28 19.52
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A.M. Reeves
Producing formation Arbuckle Depth to top 3700' Bottom 3712' Total Depth of Well 3712 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water with show of oil.	3700	3712	5 $\frac{1}{2}$ "	3701 $\frac{1}{2}$ '	2880'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with chat from 3540' to 3475'
dumped 5 sks. cement at 3475' with dump bailer.
Pumped plug to 260' in 8 5/8" csg. Pumped
60 sks. drlg. mud (42 aquagel / 18 sks. baroid)
and 75 sks. cement in 8 5/8" surface. Cut off
8 5/8" csg. at bottom of cellar. Dumped 5 sks.
cement to fill and cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drlg. Co., Inc.
Address 1307 $\frac{1}{2}$ Main St.
Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
H.O. Lynch (employee of owner) or (owner/operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H.O. Lynch*
1307 $\frac{1}{2}$ Main, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7 day of May, 19.52

My commission expires July 9, 1952

22-7877-B 4-49-10M

PLUGGING
FILE SEC 15 T 21 R 14 W
BOOK PAGE 8 LINE 24

RECEIVED
STATE CORPORATION COMMISSION
MAY - 8 1952
5-8-1952
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

ANSCHUTZ DRILLING COMPANY, INC.
 NO. 1 ANSHUTZ
 CW/2 NW NE SECTION 15-21S-14W
 STAFFORD COUNTY, KANSAS

<u>FROM</u>	<u>TO</u>	
0	280	Sand
280	314	Shale and Shells
314	840	Sand, Shale, Red Bed and Shells
840	865	Anhydrite
865	1780	Shale and Shells
1780	2210	Lime and Shale
2210	2465	Shale
2465	2615	Shale and Shells
2615	3120	Shale and Lime
3120	3240	Lime
3240	3305	Lime and Shale
3305	3348	Shale
3348	3405	Shale and Lime
3405	3605	Lime
3605	3620	Lime and Shale
3620	3640	Chert
3640	3658	Shale and Lime
3658	3678	Shale
3678	3693	Sand and Shale
3693	3704	Shale and Lime
3704		Total Depth

COMMENCED: 3-8-52
 COMPLETED: 3-20-52

CASING RECORD;
 8-5/8" surface casing set at 314' with 300 sacks cement and 5 sacks calcium chloride.
 5-1/2" casing set at 3704' with 125 sacks cement.

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Anschutz Drilling Company #1 Anshutz, located CW/2 NW NE Section 15-21S-14W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *Leon L. Mehler*
 Leon L. Mehler

Subscribed and sworn to before me this 25th day of March, 1952.

My Commission Expires: May 24, 1952

Wilma V. Shipman
 Notary Public

PLUGGING
 FILE SEC 15.21 RUCW
 BOOK PAGE 8 LINE 39

APR 12 1952
 DIVISION
 Kansas