


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 P. O. BOX 17027
 WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Stafford County, Sec. 33 Twp. 21 Rge. 14W (X) x (W)
 C NW SW NE



Locate well correctly on above Section Plat

Location as "NE/CNWxSWx" or footage from lines _____
 Lease Owner H. A. Chapman Investments
 Lease Name KRAMPE Well No. 4
 Office Address 404 Cities Service Building, Tulsa, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed February 23 19 75
 Application for plugging filed February 23 19 75
 Application for plugging approved February 23 19 75
 Plugging commenced February 23 19 75
 Plugging completed February 23 19 75
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Bieberstein
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3834 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 275' with 35 sack cement thru drill pipe.
Top plug @ 40' with 1/2 sack hulls and 10 sack cement. 2 sack cement in rat hole

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Duke Drilling Co.
 Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON, ss.
Leonard Williamson (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
P. O. Box 823, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 19 75

My commission expires April 11, 1978
Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 1-26-1975 2-26-1975
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: February 15, 1975
 DATE COMPLETED: February 23, 1975

H. A. Chapman Investments
 KRAMPE # 4
 C NW SW NE Sec. 33-T21S-R14W
 Stafford County, Kansas

ELEVATION 1945 K.B.

0 - 240'	Sand
240 - 620'	Shale, Sand
620 - 855'	Red Bed
855 - 880'	Anhydrite
880 - 1620'	Red Bed, Shale
1620 - 3309'	Lime and Shale
3309 - 3314'	Shale
3314 - 3332'	Lime and Shale
3332 - 3347'	Lime
3347 - 3428'	Shale
3428 - 3440'	Lime and Shale
3440 - 3652'	Lime
3652 - 3678'	Lime and Shale
3678 - 3738'	Shale, Lime, Chert
3738 - 3774'	Chert
3774 - 3824'	Shale
3824 - 3834'	Dolomite
3834'	RTD

FORMATION TOPS

Anhydrite	855
Heebner	3309
Toronoto	3332
Douglas	3347
Brown Lime	3428
Kansas City	3440
Base K.C.	3652
Cong.	3678
Viola	3738
Simpson Shale	3774
Arbuckle	3824
RTD	3834

SURFACE PIPE:

Set 294' of 8 5/8", 28# pipe
 w/275 sack 50/50 Pozmix, 2% Gel,
 3/8 cc.

AFFIDAVIT

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 25th day of February 1975.

Deborah M. Hague
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED
 STATE CORPORATION COMMISSION

FEB 26 1975
 CONSERVATION DIVISION
 Wichita, Kansas