

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

**WELL PLUGGING RECORD**

Stafford County, Sec. 19 Twp. 21S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SE NE SE

Lease Owner Tennessee Gas Transmission Company

Lease Name William McCrary "A" Well No. 4

Office Address P. O. Box 163 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed March 6, 1946

Application for plugging filed December 29, 1959

Application for plugging approved December 30, 1959

Plugging commenced February 1, 1960

Plugging completed February 12, 1960

Reason for abandonment of well or producing formation Well has reached economic limit

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Arbuckle Depth to top 3561 Bottom Present Total Depth of Well 3577 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	314'	0
				7"	3565'	2224'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 2-1-60. Plugging completed 2-12-60. Measured into total depth 3577'. Plugged off bottom. Sanded back to 3550' and dumped 5 sacks of cement (3550-3535'). Measured in on top of plug (3530'). Pushed plug to 3140'. Put in 15' of sand and dumped 5 sacks of cement (3140'-3110'). Worked and shot pipe. Circulated and spotted 50 barrels of oil. Shot 7" casing at 2224'. Pulled and laid down pipe. Plugged hole with mud: Mudded to 300'. Set 10' rock bridge. (290'). Dumped 25 sacks of cement (290'-215'). Mudded hole to 55'. Set 10' rock bridge (55'-45'). Capped the well with 15 sacks of cement. (45'-0').

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a/ Forbes Casing Pulling Company

Address P. O. Box 221 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss. Glen E. Armour (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

P. O. Box 163 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 1960

My commission expires October 13, 1962

John L. ... Notary Public.

STATE CORPORATION COMMISSION

FEB 17 1960

CONSERVATION DIVISION

2-17-1960