


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 19 Twp. 21 Rge. 14 (E) W (W)
Location as "NE/CNWKSW" or footage from lines NE (NE) SW
Lease Owner Petroleum Management Inc. SE
Lease Name Fischer Well No. 4
Office Address P.O. Box 922 Great Bend, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____
Application for plugging filed Jan. 1 19 49
Application for plugging approved Aug. 22, 19 67
Plugging commenced Not. 30 19 67
Plugging completed Feb. 18, 19 68
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	297'	None
				5 1/2	3609'	2736'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3550' to 3250'. Mixed and dumped 5 sx. of cement from 3250' to 3210'. Pulled casing. Mudded to 280'. Set 10' rock bridge from 280' to 270'. Dumped 4 yds. of ready mixed cement from 270' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.
Address P.O. Box 1082 Great Bend, Ks.


STATE OF KANSAS, COUNTY OF BARTON, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James H. Fletcher
Box 422 Great Bend, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1968

My commission expires June 30, 1971



FORMATION RECORD

Name of Strata	Top	Bottom	Sought Height	Remarks
Surface sand & shells	0	75		
Shale & shells	75	105		
Sand	105	140		
Shale & red bed	140	280		
Shale & shells	280	306		
Red bed & shells	306	615		
Red Bed & shale	615	985		
Red bed	985	960		
Shale & shells	960	1200		
Shale & lime	1200	1310		
Shale & shells	1310	1460		
Salt & shale	1460	1520		
Lime & shale	1520	1665		
Lime	1665	1750		
Broken lime & shale	1750	1860		
Lime & shale	1860	1995		
Lime	1995	2120		
Lime & shale	2120	2370	2650' OK	
Lime broken	2370	2910		
Lime & shale	2910	2965		
Lime	2965	3030		
Shale & lime	3030	3090		
Lime	3090	3132		
Shale	3132	3138		Heehner
Lime	3138	3144		
Shale	3144	3152		
Lime	3152	3166		
Shale	3166	3265		
Lime	3265	3272		
Lime & shale	3272	3292		
Lime	3292	3296		
Shale	3296	3299		
Lime	3299	3311	3305' OK	
Shale & lime	3311	3320		
Lime	3320	3334		
Lime & shale	3334	3346		
Lime	3346	3396		

RECEIVED
 STATE MINERAL CORPORATION COMMISSION
 AUG 21 1967
 CONSERVATION DIVISION
 Wichita, Kansas

FORMATION RECORD

FISHER #4

Page #2

Name of Strata	Top	Bottom	Depth Feet	Remarks
Lime	3422	3431		
Sandy lime	3431	3437		
Lime	3437	3455		Porosity & show of oil 3151' to 3154'
Shale	3455	3460		
Sandy lime	3450	3480		
Lime	3480	3491		
Shale	3494	3500		
Lime	3500	3511		
Cherty lime	3511	3541		Some pin point pores very light show of oil samples from top 10'
Shale & sandy dolomite	3541	3585		
Dolomite	3585	3610	Total depth,	Arbuckle.

RECEIVED
 OIL & GAS CORPORATION
 AUG 21 1961

CONSERVATION DIVISION
 Wichita, Kansas