

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-185-22,667.0000

LEASE NAME RETA

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

1880 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 19 TWP. 21S RGE. 12 (K) or (W)

COUNTY Stafford

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Kansas 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 4-27-90

Plugging Commenced 4-27-90

Plugging Completed 4-27-90

The plugging proposal was approved on April 27, 1990 (date)

by Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	302'	8 5/8"	302'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

50 sx. @ 720', 40 sx. @ 330', 10 sx. @ 40', 15 sx. in rathole (115 sx. 60/40 Pozmix, 6% Gel)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P. O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson  
 Greg Davidson

(Address) Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 90



My Commission Expires: 5-20-93 Bessie M. DeWerff  
 Notary Public  
 Bessie M. DeWerff

DRILLER'S WELL LOG

COMMENCED: 4-20-90  
 COMPLETED: 4-27-90  
 L. D. DRILLING, INC.

RETA #1  
 100' S. E/2 NE SW  
 Sec. 19-21S-12W  
 Stafford County, Kansas

0 - 302 Surface Sand  
 302 - 750 Red Bed  
 750 - 1285 Shale  
 1285 - 2250 Shale W/Lime  
 2250 - 3640 Lime & Shale

Elevation: GR 1864' KB 1869'

FORMATION DATA (Sample)

Anhy 688-705  
 Heebner 3130 (-1261)  
 Toronto 3148 (-1279)  
 Douglas 3163 (-1294)  
 Brn. Lm 3261 (-1392)  
 L K/C 3277 (-1408)  
 B K/C 3497 (-1628)  
 Con.Cht 3506 (-1637)  
 Con.Shl 3522 (-1653)  
 RTD 3640 (-1771)

CASING:

8 5/8" set @ 302' W/200 sx.  
 60/40 Pozmix, 2% Gel, 3% CC

A F F I D A V I T

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss


GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson  
 Greg Davidson

Subscribed and sworn to before me this 31st Day of May, 1990.

My Commission expires: 5-20-93

Bessie M. DeWerff  
 Notary Public: Bessie M. DeWerff



MAY 4 1990