


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 19 Twp. 21 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
NE NE NE

Lease Owner W. L. Kirkman, Inc.
Lease Name Hall #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/30/77 _____ 19____
Plugging completed 5/10/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3541
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	308	none
				4 1/2"	3538	2204'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3350' and mixed and ran 4 sacks cement. Shot pipe at 2920', 2820', spotted 40 bbls. oil and pumped plug to 2760'. Shot pipe at 2600', 2415', 2200', pulled 83 joints. Squeezed hole with 3 sacks hulls, 20 sacks gel, released plug and displaced with 100 sacks 50/50 posmix, 2% gel.

PLUGGING COMPLETE.

MAY 16 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 77

Margaret Melcher
Notary Public.

My commission expires _____



REVOLVED

TRANSIT CORPORATION

15.185.13081.0000

GENERAL

E. P. HALL NO. 1
NE NE NE Sec. 19-21E-1E4
Stafford County, Kansas

Pot. 135130 New

Comm. 10-18-50
Conf. 12-13-50

FORMATION	FROM	TO
Sand & Shale	0	230
Red Bed	230	295
Red Bed & Shells	295	675
Anhydrite	675	705
Shale & Shells	705	850
Shale, Shells & Salt	850	1345
Shale & Shells	1345	1550
Lime & Shale	1550	1860
Lime	1860	1960
Lime & Shale	1960	2065
Lime & Sand	2065	2160
Shale	2160	2195
Lime & Shale	2195	2370
Shale	2370	2730
Shale & Lime	2730	2845
Shale	2845	2895
Lime	2895	3080
Lime & Shale	3080	3250
Lime	3250	3310
Lime & Shale	3310	3370
Lime	3370	3431
Lime soft-slight odor	3431	3442
Lime	3442	3452
Lime & Shale	3452	3475
Chert	3475	3502
Shale & Lime	3502	3541
Total Depth		3541

2-5/8" ~~C.S.~~ 309'. Cemented
with 175 sacks cement

RECEIVED
STATE COLLEGE DIST. COMMISSION

APR 19 1977

CONSERVATION DIVISION
4-1/2" C.S. 3330'. Cemented
with 125 sacks cement

I hereby certify the foregoing to be a true and accurate Driller's
Log of the formations encountered in the above well.

TRANSIT CORPORATION

By L. J. Kruse
L. J. Kruse, Asst. Secy.

Subscribed to and sworn to before me this 22nd day of December, 1950.

My commission expires:

11-17-53

Margaret Kier DeBe
Notary Public

over Perfs 3376-82