


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plot

Stafford County, Sec. 19 Twp. 21S Rge. 4 (W)
Location as "NE/CNW/SW" or footage from lines S/2 - NE/4 - NE/4
Lease Owner Wayne L. Kirkman
Lease Name E. B. Hall Well No. 2
Office Address Box 143 Great Bend Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-26 19 51
Application for plugging filed 4-19 19 74
Application for plugging approved 19
Plugging commenced 5/3/74 19
Plugging completed 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 3-15 19 72
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Arbuckle Depth to top 3580 Bottom 3600 Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Surface</u>		<u>0</u>	<u>300</u>	<u>8 5/8</u>	<u>Cem.</u>	<u>200 SX</u>
		<u>0</u>	<u>3580</u>	<u>5 7/16</u>		<u>600</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped Cement to 2800' with Halliburton

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 - 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling
Address Box 373 Geneseo Kansas 67444


STATE OF KANSAS, COUNTY OF RICE, ss.
George A. Nicholas (employee of owner) or (owner or operator) of the above-described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas

(Address)

Sworn to before me this 7th day of May, 19 74



September 24, 1974

Warren H. Laughlin Notary Public.

TRANSIT CORPORATION

E.B. HALL #2

Center S/2 NE/4 NE/4
 Sec. 19-21S-12W
Stafford County, Kans.

Wayne L. Kirkman

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand & Gravel	0	235	8 5/8" C.S.A. set 300' with 200 Sacks Cement.
Sand & Shale	235	308	
Red Bed & Shells	308	670	
Shale	670	677	
Anhydrite	677	705	
Shale Shells	705	985	
Shells Salt Shale	985	1065	
Shale & Shells	1065	1280	
Salt & Shale	1280	1455	
Shale & Salt	1455	1520	
Lime & Shale	1520	1620	
Lime Sandy	1620	1720	
Sandy Lime & Shale	1720	1845	
Lime & Shale	1845	1960	
Shale Lime	1960	2060	
Lime & Shale	2060	2165	
Shale & Lime	2165	2350	
Shale Shells	2350	2510	
Shale & Lime	2510	2620	
Lime & Shale	2620	2740	
Shale Lime	2740	2925	
Lime & Shale	2925	3005	
Shale Lime	3005	3055	
Lime	3055	3120	
Shale & Lime	3120	3265	
Lime	3265	3300	
Lime & Shale	3300	3345	
Lime Shell	3345	3400	
Lime	3400	3434	
Lime & Shale	3434	3475	
Shale	3475	3480	
Lime & Shale	3480	3525	
Shale & Lime	3525	3555	
Lime & Shale	3555	3600	

Total Depth 3600'

Run 75 Jts. 5-9/16" Casing
 & Cemented with 100 sacks
 cement. Set Pipe @ 3580'-
 20' off bottom.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 22 1974
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing to be a true and accurate Drilling
 Log of the formations encountered in the above well.

TRANSIT CORPORATION

By: L. J. Kruse
 L. J. Kruse, Asst. Secy.

Subscribed and sworn to before me this 26th day of March, 1951.

Harold Taylor
 Notary Public

My Commission Expires: 3-13-53