

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21070-00-00

LEASE NAME Greiner

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 17 TWP. 28S RGE. 16W (E) or (W)

COUNTY Kiowa

Date Well Completed

Plugging Commenced 5-19-89

Plugging Completed 5-25-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Case Oil & Gas

ADDRESS 1251 S. Clay #3 Liberal, Kanas 67901

PHONE#(316) 626-8423 OPERATORS LICENSE NO. 9158

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4855'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	420'	none
				5-1/2"	4853'	2549'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 4660', and 5 sacks cement. Shot pipe @3612', 3398', 3222', 3016', 2798', 2549', pulled a total of 71 joints of 5-1/2" casing. Plugged surface with 400# bulls, 10 gel, 50 cement, 10 gel, 100# bulls, plug and 120 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. RECEIVED 950

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 2nd. day of June, 19 89

[Signature]
Notary Public

My Commission Expires:



ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

WELL LOG



WELL NAME: GREINER #1

WELL LOCATION: NE-NE NW

SEC. 17-28S-16W, KIOWA COUNTY, KS.

OPERATOR: CASE OIL & GAS

COMMENCED: 10-26-84

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 11-3-84

10 Jts. J-55 8 5/8" 24 wt. New
CASING RECORD: set at 411' 300 sks
200 lightweight-100 common 2% gel 3%cc.
146 jts. J-55 5 1/2" 14 wt. 10 New
136 used set at 4955' 100 sks surfll

FORMATION:

FROM:

TO:

Red Bed	0	226'
Sand-Red Bed	226'	420'
Red Bed	420'	2207'
Lime-Shale	2207'	4956'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
E-NE NW, SEC. 17-28S-16W, KIOWA COUNTY, KANSAS TO THE BEST OF MY

KNOWLEDGE AND BELIEF.

RECEIVED
STATE CORPORATION COMMISSION
FEB 05 1985
CONSERVATION DIVISION
Wichita, Kansas

ALDEBARAN DRILLING CO., INC.
WAYNE L. KIRKMAN
PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 7TH DAY OF NOVEMBER, 1984.

KATHLEEN G. QUINN
STATE NOTARY PUBLIC
APPOINTMENT EXPIRES
My Appt. Exp 3-20-87
MARCH 20, 1987

Kathleen G. Quinn
KATHLEEN G. QUINN