

WELL PLUGGING RECORD

**Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat**

Barton	County. Sec. 5	Twp. 16	Rge. 13	(E) West(W)
Location as "NE¼NW¼SW¼" or footage from lines 1320' S. & 990' W. of E/4 Cor.				
Lease Owner.....	Cities Service Oil Company			
Lease Name.....	Kosar			Well No. 5
Office Address.....	Bartlesville, Oklahoma			
Character of Well (Completed as Oil, Gas or Dry Hole).....	Dry Hole			
Date, well completed.....	December 5,			193 41
Application for plugging filed.....	December 5,			193 41
Application for plugging approved.....	December 5,			193 41
Plugging Commenced.....	December 5,			193 41
Plugging Completed.....	December 5,			193 41
Reason for abandonment of well or producing formation.....	Dry Hole			

If a producing well is abandoned, date of last production.....193.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well..... C. T. Alexander
Producing formation..... Dry in Arbuckle..... Depth to top..... 3394'..... Bottom..... 3415'..... Total Depth of Well..... 3415'..... Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole filled with heavy mud from 3415-3332. 15 sacks cement placed at 3332' (bottom of 8-5/8" casing). 10 sacks cement placed top of hole.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... R. C. Hauber 12-2
Address..... Cities Service Oil Company
..... Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C. J. Kerwin (employee of owner) ~~(employee of operator)~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Great Bend, Kansas

SUBSCRIBED AND SWORN to before me this 15 day of December, 1941

My commission expires..... My Commission Expires Sept. 26, 1942

17-6058 10-38--5M

Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well. No. 5 Farm Kosar
 Location 1320' south & 990' west of N/4 Corner Sec. 5 T. 16 R. 13W
 Elevation 1929 County Barton State Kansas
 Drig. Comm. November 24, 1941 Contractor R. W. Rine Drilling Company
 Drig. Comp. December 4, 1941 Acid None
 T. D. 3415' Initial Prod. Dry - Plugged and Abandoned

CASING RECORD:


8-5/8" O 332' cas. 115 sx Victor,
 4 sx Aquagel and
 200# C. C.

FORMATION RECORD:

lime, shale & shells	0-260
shale & shells	1260
shale & salt shells	1500
shale & shells	1620
broken lime & shale	1739
lime & shale	1845
shale & shells	1949
lime & shale	2027
shale & shells	2670
lime & shale	2938
lime	2990
lime & shale	3045
lime	3070
lime & shale	3161
lime	3260
lime & chert	3290
lime	3350
lime & shale	3400
lime	3415 T. D.

Top Lansing	3136'
Top Arbuckle	3394'
Penetration	21'
Total Depth	3415'

Syfo:	500'	0°
	1000'	0°
	1500'	0°
	2000'	0°
	2500'	0°
	3000'	0°



5-16-13W
 16-16-13W