

STATE OF KANSAS
STATE CORPORATION COMMISSION
240 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.30370.0000

LEASE NAME Sparks

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 6 TWP. 21 RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed 12-19-66

Plugging Commenced

Plugging Completed 12-5-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G.Holl Company

ADDRESS P.O. Box 158 Belpre, Ks. 67519

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3448'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	258'	none
				4 1/2"	3426'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged well with 300# hulls, 225 sacks 60/40 8% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G.Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 6 day of Decmeber, 1991

My Commission Expires:

IRENE HERZBERG
Notary Public
State of Kansas
My Appt. Exp. Aug. 24, 1993

W E L L L O G

DATE COMMENCED: December 11, 1966
 DATE COMPLETED: December 19, 1966

F. G. HOLL
 SPARKS #2
 E/2 E/2 SW/4
 Sec. 6-21s-11w
 Stafford County, Kansas

ELEVATION: 1818 K.B.

0	-	70'	Sand & Clay
70	-	230'	Clay & Sand
230	-	578'	Red Bed
578	-	607'	Anhydrite
607	-	1560'	Shale & Shells
1560	-	2000'	Lime & Shells
2000	-	2690'	Shale & Shells
2690	-	3005'	Lime
3005	-	3009'	Shale
3009	-	3033'	Lime - Shale
3033	-	3128'	Shale
3128	-	3145'	Lime & Shale
3145	-	3414'	Lime
3414	-	3445'	Dolomite
3445			RTD

FORMATION DATA

Anhydrite	578
Heebner	3005
Brown Lime	3128
Lansing	3145
Arbuckle	3414
RTD	3445

SURFACE CASING: Set 8-5/8"
 pipe at 258' with 225 sacks cement

PRODUCTION CASING: Set 4 1/2"
 pipe at 3426' with 75 sacks
 pozmix - 1/4# floreal

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.


L. O. Chubb of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.


 L. O. Chubb

Subscribed and sworn to before me this 22 day of December 1966.

My Commission Expires:

April 11, 1970


 Dorothy M. Hague NOTARY PUBLIC

RECEIVED
 KANSAS CORPORATION COMMISSION

OCT 7 1991

CONSERVATION DIVISION
 WICHITA, KS