

15.185.12452.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 7 Twp. 21S Rge. 11W (E) (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. Cen. NE $\frac{1}{4}$ SW $\frac{1}{4}$
 Lease Owner Leonard Isern, George Angle, Adkins Drilling Co. Inc.
 Lease Name Schloctermeyer Well No. 1
 Office Address P O Box 724 Great Bend, Kansas.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed April 17th 19 53
 Application for plugging filed April 17th 19 53
 Application for plugging approved April 17th 19 53
 Plugging commenced April 17th 19 53
 Plugging completed April 18th 19 53
 Reason for abandonment of well or producing formation Dry Hole
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives, Pratt, Kansas.
 Producing formation Depth to top Bottom Total Depth of Well 3547 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand and surface clay	none	0	271	8 5/8"	264'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with Heavy Mud from 3547' up to 260', permanent plug enstalled and cemented with 20 sacks of cement. Heavy mud to 20' and permanent plug enstalled and cemented with 10 sacks of cement to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Adkins Drilling Company, Inc.
Address P O Box 724 Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

Jim Adkins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Adkins
P O Box 724 Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 19 53

My commission expires 2-29-1956 Notary Public.

PLUGGING
FILE SEC 7 T 21 R 11W
BOOK PAGE 94 LINE 19

APR 21 1953
4-21-53

15.185.12452.0000

DRILLERS LOG

Operator- Leonard I Isern, George Angle, Adkins Drilling Company, Inc.

Contractor- Adkins Drilling Company, Inc.

Lease- Schlootermeyer No. 1 Sec. 7-21S-11W. Stafford County, Kansas.

Formation	From	To	Formation	From	To
Sand and Shale	0	245			
Sand and Clay	245	271			

Set 264' of 8 5/8" casing and cemented with 300 sacks cement and 100 # Calcium Chloride.

Plug at	225	226
Cement	226	265
Open Hole	265	271
Clay and Red Bed	271	635
Red Bed and Shale	635	1265
Shale	1265	1482
Shale & Lime	1482	3045
Lime & Shale	3045	3290
Shale & Lime	3290	3305
Lime & Shale	3305	3547

2. D. 3547'
Hole Dry and abandoned @ 3547' and plugged.

The following above Drillers Log is true and correct to the best of my knowledge and belief.

Adkins Drilling Company, Inc.

By Jim Adkins
President.

Subscribed and Sworn to before me this 20th day of April 1953.

Pauline B. Adkins
Notary Public

My Commission expires 2-29-1956.

PLUGGING
FILE SEC 7 T 21 R 11W
BOOK PAGE 94 LINE 19

CONF