

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 7 Twp. 21S Rge. 11W (Ex.) (W)
Location as "NE/CNW%SW%" or footage from lines NW NW SW
Lease Owner R. W. Shields and Prime Drilling Company
Lease Name Schlochtermeyer Well No. 1
Office Address 814 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 15 19 59
Application for plugging filed August 15 19 59
Application for plugging approved August 15 19 59
Plugging commenced August 15 19 59
Plugging completed August 15 19 59
Reason for abandonment of well or producing formation no oil or gas in
commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 3528 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 275'. Set Plug #1 at 275' with 20 sacks cement.
Filled hole with extra heavy rotary mud from top of plug #1 to 40'. Set Plug #2 at 40' cemented with 10 sacks cement. Put 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1959 8-19-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 59

My commission expires Sept. 30, 1959 Darlene May Notary Public.

PLUGGING
FILE SEC 7 T 21 R 11W
BOOK PAGE 62 LINE 6

ROTARY DRILLING LOG

OPERATOR: R. W. Shields & Prime Drilling Company
 No. 1 Schlochtermeyer
 NW NW SW Sec. 7-21S-11W,
 Stafford County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 7/31/59
 COMP: 8/15/59

Remarks: Set 8-5/8" surface casing
 at 280' cemented with
 250 sacks HA 500 cement.

Formations:

Surface Sand & Soil	60'
Sand, gravel & clay	190'
Red Bed & Shale	280'
Shale & Red Bed	585'
Anhydrite	610'
Red Bed & Shale	670'
Shale & Shells	1205'
Shale	1470'
Shale & Lime Streaks	1560'
Brown Lime	1700'
Lime & Shale	2080'
Lime	2110'
Shale & Lime Shells	2245'
Shale & Lime	2660'
Lime	2685'
Lime & Shale	2823'
Lime	3095'
Lime & Shale	3155'
Lime	3400'
Cherty Lime	3434'
Chert Lime & Shale	3484'
Chert & Lime	3511'
Cherty Lime	3528'
Rotary Total Depth (D&A)	3528'

RECEIVED
 STATE CORPORATION COMMISSION

AUG 19 1959

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

PRIME DRILLING COMPANY

R.R. McNicol
 R. R. McNicol

