

STATE OF KANSAS
STATE CORPORATION COMMISSION
1 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-19009-00-00

LEASE NAME Schloctermeier

RECEIVED

MAY 23 2002 5-23-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 4

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 7 TWP. 21S RGE. 11W (E) or (W)

COUNTY Stafford

KCC WICHITA
LEASE OPERATOR BEREXCO, INC.

ADDRESS P.O. Box 20380 Wichita, Kansas 67208

PHONE (316) 254-3311 OPERATORS LICENSE NO. 5364

Date Well Completed _____

Character of Well Oil

Plugging Commenced 5-14-02

(If, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-16-02

A plugging proposal was approved on _____ (date)

Scott Alberg (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3495

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	276'	None
				4-1/2"	3435'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each. Plugged off bottom with sand to 3300' and 4 sacks cement. Shot casing @2000' and 1800'. Ran 2" tubing to 600', pumped 10 sacks gel, 200# bulls and 50 sacks cement, pulled tubing to 280', pumped 50 sacks cement, pulled to 40' and circulated 20 sacks cement 60/40 pos 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BEREXCO, INC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of May 2002

Irene Herzberg
Notary Public

My Commission Expires:

