

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
1 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-13186 - 03 - 00

LEASE NAME Schloctermeier

WELL NUMBER 3

RECEIVED

MAY 23 2002 5-23-02

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

400 Ft. from E Section Line

KCC WICHITA

OPERATOR BEREXCO, INC.

SEC. 7 TWP. 21S RGE. 11W (E) or (W)

ADDRESS P.O. Box 20380 Wichita, Kansas 67208

COUNTY Stafford

PHONE (316) 254-3311 OPERATORS LICENSE NO. 5363

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 5-9-02

(If, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-14-02

Is a plugging proposal was approved on \_\_\_\_\_ (date)

Richard Lacey (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3535'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	254'	None
				5-1/2"	3495'	2020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3340' and 5 sacks cement. Shot casing @2400', 2200' and 2020'. Ran 2" tubing to 600', pumped 10 sacks gel and 50 sacks cement, pulled tubing to 280', pumped 50 sacks cement, pulled to 40' and circulated 20 sacks cement 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BEREXCO, INC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of May 2002

[Signature]  
Notary Public

My Commission Expires:



OK