


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 30 Twp. 21 Rge. (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$ 330' from W 300' from S
Lease Owner Grant Oil Company
Lease Name Hullman Well No. 1
Office Address 814 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 2 19 51
Application for plugging filed April 24 19 52
Application for plugging approved April 24 19 52
Plugging commenced April 26 19 52
Plugging completed May 3 19 52
Reason for abandonment of well or producing formation Went dry
If a producing well is abandoned, date of last production Dec. 16 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merrill Rives
Producing formation Simpson Sand Depth to top 3503' Bottom 3514' Total Depth of Well 3514' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water	0	185	8 5/8	200	None
Simpson sand	Oil	3503'	3514'	5 1/2	3506'	2428'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

When well was drilled there was 200' of surface pipe (8 5/8"). Cement was circulated. Oil String (5 1/2") was set at 3506' with 100 Sacks of cement. On abandonment it was plugged back from 3514' to 3495' with sand. From 3495' to 3460' with 5 sacks of cement. From 3460' to 200' with heavy mud. From 200' to bottom of the cellar with 55 sacks of cement.

Hole was squeezed with Halliburton pump truck with 25 sacks of mud and 55 sacks of cement with a 8 5/8" plug between mud and cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this report)
Name of Plugging Contractor Grant Oil Company
Address 814 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, W. A. Grant (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)
814 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of May 19 52

My commission expires Feb. 29, 1956

Notary Public.

PLUGGING
FILE SEC 30 T 21 R 11
BOOK PAGE 13 LINE 35

HULLMAN NO. 1

SW/4 SW/4 SE/4 Sec. 30-21S-11W, Stafford County, Kansas

Rigging up Rotary Tools 1-16-51
Tearing down Rotary Tools 2-3-51Run 5 Jts. 200' of 8 5/8" surface pipe.
Cemented with 100 sx cement.
Run 109 Jts. 5 1/2" Oil String. Set at
3506' and cemented with 100 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay and sand	0	40
Sand and redbed	40	198
Redbed and shale	198	455
Shale and shell	455	555
Anhydrite	455	590
Shale and shell	590	1375
Lime (Ft. Riley)	1375	1585
Lime and shale	1585	1860
Shale and shells	1860	1925
Shale and shell	1925	2050
Shale and lime	2050	2770
Lime	2770	2985
Lime and iron	2985	3055
Lime	3055	3155
Lime and shale	3155	3182
Lime (Lansing)	3182	3215
Lime	3215	3320
Sandy Break	3320	3328
Dense Lime	3328	3350
Lime and shale	3350	3410
Lime	3410	3465
Shale-Conglomerate	3465	3480
Conglomerate	3480	3495
Simpson Sand	3495	3516 Total Depth

I, W. A. Grant, hereby certify that the above Log is true and correct,
to the best of my knowledge and belief.



Subscribed and sworn to before me this 16 day of May, 1952.

RECEIVED
STATE CORPORATION COMMISSIONER

MAY 17 1952


Notary Public

My commission expires: Feb. 29, 1956
CONSERVATION DIVISION
Wichita, Kansas

