

WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
809 Bitting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

Stafford County. Sec. 30 Twp. 21 Rge. (E) 11 (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. W/2. NW/4. NW/4
 Lease Owner Aladdin Petroleum Corporation
 Lease Name McMillan Well No. 1
 Office Address 809 Petroleum Building, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed July 9, 19 50
 Application for plugging filed July 9, 19 50
 Application for plugging approved July 9, 19 50
 Plugging commenced July 9, 19 50
 Plugging completed July 9, 19 50
 Reason for abandonment of well or producing formation No shows



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production.....19.....
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3600 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	253	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with mud T.D. 3620 to 250' @
 bottom of surface casing.
 Set wood plug and 15 sacks cement @ 250'
 Filled hole with mud.
 Set wood plug and 10 sacks cement 30'
 below bottom of cellar.

RECEIVED
 Conservation Div.
 AUG 11 1950 8-11-50
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Correspondence regarding this well should be addressed to Aladdin Petroleum Corporation
 Address 809 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. M. JOHNSON (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
809 Petroleum Building, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 10th day of August, 19 50

My commission expires April 23, 1952

[Signature] Notary Public.

PLUGGING
 FILE SEC 30 TWP 21 R 11 W
 BOOK 15 LINE 31

WELL LOG

J. D. Ferrell Drilling Co., Inc. et al
MC MILLAN # 1

CW/2 NW/4 NW/4
Sec. 30-21-11W
Stafford County, Kansas

Total Depth: 3620'
Comm: 6-27-50 Comp: 7-9-50
Contractor: J. D. Ferrell Drilling Co., Inc.
Rotary: 0 - 3620'

Elevation: 1816 K.B.
Production: D & A

Casing Record: 253.43' of 8 5/8" surface casing cemented w/175 sx cement.

Figures Indicate Bottoms of Formations:

Cellar	5
Sand	100
Shale & Shell	251
Red Bed & Shell	568
Anhydrite	595
Shale	630
Red Bed & Shale	1010
Salt & Shell	1060
Shale & Shell	1410
Shale	1465
Lime	1685
Shale & Lime	1810
Shale & Sand	1825
Lime & Sand	2090
Lime	2120
Shale & Lime	2330
Shale & Shells	2495
Shale & Lime	2625
Shale	2830
Lime	3070
Shale & Lime	3195
Lime	3490
Lime & Shale	3503
Conglomerate	3525
Shale - Simpson	3550
Lime - Arbuckle	3590
Cherty Lime	3596
Lime	3600
Cherty Lime	3620

Tops:

Anhydrite	568
Topoka	2775
Hesbner	3070
Brown Lime	3197
Lansing-Kansas City	3212
Conglomerate	3490
Arbuckle	3565

Total Depth 3620

Total Depth 3620 D & A


RECEIVED

Conservation Dept.

AUG 11 1950

STATION

We hereby certify this to be a correct and accurate log of the above described well as shown on the Daily Drilling Reports.



J. D. FERRELL DRILLING COMPANY, INC.

By: J. D. Ferrell

Subscribed and sworn to before me this 2nd day of August, 1950.

Frances Buchanan

My commission expires Dec. 2, 1953.