

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 7-37
LOCATION SW SW SE
SEC. 10 TWP. 21 RGE. 25W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Rabger Ploger
Operator Hilton Dry Co Inc Address Box 108 Great Bend Kansas
Field _____ County Woodsman
Total Depth 4480 Feet.
Plugging Contractor Coe Pipe Pulling Co
Plugging Contractor's License No. 2
Address Great Bend Kansas

(Describe Briefly the manner in which the well was plugged)

8 1/2" 280' C. W. C. 5 1/2" 4478' emit 150# P.B. Plug and
Cement. Ref 4334' to 4360' hole filled with sand
to 4320' run 5 1/2" cement with dump fibres
Pulled 5 1/2" to 850' Pumped 25# Jell Mud through 5 1/2"
Mud to 550' Pumped 75# cement 550' to 200'
to protect water well that is near JO 426'
Mud to 35' set Plug run 10# cement cap.

M. L. Rivers
District Conservation Agent

Date 5-2-57

PLUGGING
FILE SEC. 10 T. 21 R. 25W
BOOK PAGE 7 LINE 37

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 - 1957 5-6-1957

CONSERVATION DIVISION
Wichita, Kansas