


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Charles L. Carlock

Complete Address: 1515 Hillcrest Road. Newton, Kansas 67114

Lease Name Rupp Well No. # 1

Location W/2 NE NE Sec. 13 Twp. 21 Rge. 2W 8 E/1 (W)

County McPherson Total Depth 3410'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Co. Inc.

Address: Great Bend, Kansas License No. # 637

Operation Completed: Hour 1 PM Day 12 Month 3 Year 70

The Above well was plugged as follows:

8 5/8"-205'-Circulated w/cement. 4 1/2"-3409'-Cemented. Plug back to 3020'.

Top Perf. 2973'. Plug bottom w/Plug, 6 Sax. cement top cement at 2900',

Hallibutton Cementing Company. Mud 2900' to 220'. Bridge 220' to 210'.

25 Sax. cement 210' to 140'. Mud 140' to 40'. Bridge 40' to 30'.

10 Sax. cement 30' to 0'. Pulled 2600'-4 1/2"-pipe,

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/17/70
INV. NO. 1595-W