

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

RECEIVED  
JAN 15 1991

CONSERVATION DIVISION

Wichita, Kansas

API NUMBER 15-055-20,950.0000 (of this well).

1-15-1991

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Lebsack Oil Production, Inc. OPERATOR'S LICENSE NO. 5210

ADDRESS P.O. Box 489, Hays, KS 67601 PHONE # (913) 625-3046

LEASE (FARM) Foster WELL NO. 2-18 WELL LOCATION E/2 SW NW COUNTY Finney

SEC. 18 TWP. 21S RGE. 34 (E) or (W) TOTAL DEPTH 4900' PLUG BACK TD         

Check One:

OIL WELL          GAS WELL          D & A X SWD or INJ WELL          DOCKET NO.         

SURFACE CASING SIZE 8 5/8" SET AT 271' CEMENTED WITH 60-40 pozmix SACKS 220

CASING SIZE          SET AT          CEMENTED WITH          SACKS         

PERFORATED AT         

CONDITION OF WELL: GOOD X POOR          CASING LEAK          JUNK IN HOLE         

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2700' w/100 sx; 2nd plug @

1270' w/80 sx; 3rd plug @ 630' w/50 sx; 4th plug @ 300' w/50 sx; 5th plug @ 40' w/10 sx;

Rathole 15 sx; mousehole 10 sx; 60-40 pozmix 6% gel 1/4# Flocel per sack.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?          IS ACO-1 FILED? No  
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10:00 a.m. 1-4-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig, Sr. PHONE # (913) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton  
(Operator or Agent)

DATE: January 14, 1991