

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-093-21,501-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Abercromble Drilling, Inc. KCC LICENSE # 5422
(owner/company name) (operator's)

ADDRESS 150 N. Main, Suite 801 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE HOULOOSE WELL# 1 SEC. 7 T. 21S R. 35W (East West)

SPOT LOCATION/QQQQ COUNTY Kearny

1980' FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

660' FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# 1996

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 307.81' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATION 3198'/3203' T.D. 5125' PPTD ANHYDRITE DEPTH 2250'-2263'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill in hole with heavy mud. 1st plug at 3010'/100 sks, 2nd plug at 2260'/50 sks, 3rd plug at 1060'/80 sks, 4th plug at 340'/50 sks, 5th plug at 40'/10 sks, 15 sks in rathole, total 305 sks.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Enclosed

If not explain why? N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Walt Brown PHONE# (316) 792-9906

ADDRESS P.O. Box 1139 City/State Clmarron, Ks. 67835

PLUGGING CONTRACTOR Abercromble RTD, Inc. KCC LICENSE # 30684

ADDRESS 150 N. Main, Suite 801 Wichita, Ks. 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6:30 p.m. on 3-30-96

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4/16/96 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature) Mark R. Galyon, Vice Preside