

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-113-20,543.0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Hess Oil Company OPERATOR'S LICENSE NO. 5663

ADDRESS P.O. Box 1009, McPherson, KS 67460 PHONE # (316) 241-4640

LEASE (FARM) Huxman WELL NO. 3 WELL LOCATION SW SE SE COUNTY McPherson

SEC. 23 TWP. 21S RGE. 2 (X) or (W) TOTAL DEPTH 3385 PLUG BACK TD N/A

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 113' CEMENTED WITH 100 SACKS

CASING SIZE 4-1/2" SET AT 3351' CEMENTED WITH 50 SACKS

PERFORATED AT None

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As per district office.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? _____
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN June 3, 1992

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

James Hess PHONE # (316) 241-4640

ADDRESS P.O. Box 1009; McPherson, KS 67460

PLUGGING CONTRACTOR Hess Oil Company LICENSE NO. 5663

ADDRESS P.O. Box 1009, McPherson, KS 67460 PHONE # (316) 241-4640

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: James H Hess
(Operator or Agent)

DATE: 5-29-92

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1992
CONSERVATION DIVISION
Wichita Kansas

Blackstone Drilling, Inc.

1184
 523 West Kansas • Phone (316) 1-1250
 McPHERSON, KANSAS 67460

15.113.20543.0000

May 30, 1978

COMPANY: JOHN J. DARRAH
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: HUXMAN #3
 LOCATION: SW/4 SE/4 SE/4 Sec. 23-21-2W,
 McPherson County, Kansas
 COMMENCED: May 22, 1978
 COMPLETED: May 29, 1978
 ELEVATION:

0	to	65	Clay & Sand
65	to	113	Blue Shale
113	to	1164	Lime & Shale
1164	to	1650	Shale & Lime
1650	to	1960	Lime
1960	to	2215	Shale & Lime
2215	to	2400	Lime & Shale
2400	to	2845	Shale & Lime
2845	to	2960	Lime & Shale
2960	to	3177	Lime
3177	to	3282	Mississippi
3282	to	3350	Shale
3350	to	3385	Sand
		3385	T. D.

Cut 12 1/2" hole to 113' and run 115' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 113'. Plug down at 12:45 A. M., May 22, 1978. Cut 7 7/8" hole to 3385'. Run 3354.8' of 4 1/2" casing, cemented with 50 sacks of cement at 3351', 34 feet off bottom. Plug down at 6:15 P. M., May 29, 1978.

TOPS: Mississippi - 2973'


Measurements taken from K. E.


CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Huxman #3, located on the SW/4 SE/4 SE/4, Section 23-21-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 30th day of May, 1978.


 Johnnie L. Schmidt - Notary Public



RECEIVED
 STATE OF KANSAS COMMISSION

JUN 1 1978

REGISTRATION DIVISION
 Wichita, Kansas

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

June 3, 1992

Hess Oil Company
Box 1009
McPherson KS 67460

Huxman 3
API 15-113-20,543
SW SE SE
Sec. 23-21-02W
McPherson County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809