

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County. Sec. 13 Twp. 21S Rge. 2 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW SE NE

Lease Owner Beacon Resources Corporation.

Lease Name Rupp Well No. 1

Office Address 312 Union Center Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 5, 19 68

Application for plugging filed May 5, 19 68

Application for plugging approved May 5, 19 68


Plugging commenced 8:00 AM, May 5, 19 68

Plugging completed 9:00 AM, May 5, 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3488 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 200'. 25 sacks cement and 1/4 sack hulls with Halliburton plug. Heavy mud to 40' and 1/4 sacks cement and 1/4 sack of hulls and 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF Kansas, COUNTY OF Rice, ss.

F. A. Wuellner (employee of owner) or (owner/cooperator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of May, 1968

BERNARD LAUDERMILK, Notary Public
Commission Expires January 22, 1970
Bernard Laudermilk Notary Public.

My commission expires _____

STERLING DRILLING COMPANY
Sterling, Kansas 67579

WELL LOG ----- RUPP #1

LOCATED: SW SE NE Section 13-21S-2W, McPherson County, Kansas

OWNER: Beacon Resources Corporation

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 27, 1968

COMPLETED: May 5, 1968

ROTARY TOTAL DEPTH: 3488'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 120 Sand and Clay	Ran 10 Joints 8 5/8" used casing, 207.67 pipe set at 219' K.B., cemented with 200 sacks
120 - 222 Clay and Shale	Pozmix #1 with HA5. Plug down at 10:00 PM by Halliburton.
222 - 500 Shale	
500 - 3015 Lime and Shale	
3015 - 3140 Lime and Chert	
3140 - 3200 Lime and Shale	
3200 - 3260 Lime	
3260 - 3358 Shale	
3358 - 3420 Lime and Shale	
3420 - 3488 Lime	Plugged