

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

~~FORMATION PLUGGING RECORD~~

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

McPherson County, Sec. 10 Twp. 21S Rge. (E) 3 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$, SW $\frac{1}{4}$, 330' fm Sth & West lines

Lease Owner Sinclair Prairie Oil Co

Lease Name A.C. Stucky

Well No. 2

Office Address Box 521, Tulsa, Okla/

Character of Well (completed as Oil, Gas or Dry Hole) gas

Date, well completed May 3 19 33

Application for plugging filed Nov. 14 19 41

Application for plugging approved Nov. 17 19 41

Plugging Commenced Nov. 16 19 41

Plugging Completed Nov. 27 19 41

Reason for abandonment of well or producing formation gas exhausted

If a producing well is abandoned, date of last production Nov, 10 19 41

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Chat Depth to top 2982 Bottom 3085 Total Depth of Well 3100 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Chat	gas	2982	3085	8-5/8" 13" OD	2985' 195'	1738' 0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 3100 - 2980' mud
- 2980 - 2962' cement 6 sx
- 2962 - 195' mud
- 195 - 165' cement 15 sx
- 165 - 20' mud
- 20 - bottom of cellar - cement 20 sx

FILE 10 21-34
BOOK 14 12-30



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Victor Chancellor

Address Box 774, Great Bend, Kans

STATE OF Kansas, COUNTY OF Barton, ss.

Victor Chancellor

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Victor Chancellor

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of December, 1941

My commission expires 6-17-43

J. W. MacFarland
Notary Public.

WELL LOG - A. C. STUCKY WELL #2
Sinclair Prairie Oil Co.

Sand	195		
Shale	550		
Shale & Lime	840		Pipe Record
Lime & Shale	1050		
Shale & Shells	1250	12 1/2"	195'
Shale & Lime	1400	8 1/4"	2985'
Lime & Slate	1500		
Shale & Shells	1700		
Lime & Shale	1800		
Hard Lime	1910		
Lime & Shale	2110		
Shale & Shells	2180		
Shale & Lime	2325		
Shale & Lime	2385		
Hard Lime	2832		
Slate & Lime	2885		
Lime	2915		
Broken Lime	2945		
Shale	2982		
Chat	3085		
Shale	3312		
Lime	3317		
Shale	3329		
Viola Lime	3359		
Green Shale	3374		
Sandy Shale	3379		
Wilcox Sand	3382		
Silicious Lime	3442		

Plugged back to 3100 to Mississippi Chat May 3, 1933.

PLUGGED
 FILE 10-21-30
 BOOK 14-15-30

RECEIVED
 NOV. 15 1941