


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County, Sec. 7 Twp. 21 Rge. 6 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C SE NW

Lease Owner F. G. Holl
Lease Name Ramsey #2 Well No. _____
Office Address Lyons, Kansas 67554
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/3/80 _____ 19____
Plugging completed 1/7/80 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3585
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	209	none
				4 1/2"	2812	2812
					3584'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3500' and ran 3 sacks cement. Loaded hole with salt water, cut off poor boy head and shot pipe at 3008', 2807', pulled 87 joints. Pumped 4 sacks hulls, 20 sacks gel, plug and 85 sacks 50-50 pos, 2% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of Jan., 19 80

Margaret Melcher
Notary Public.

My commission expires _____



RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1980

CONSERVATION DIVISION
Wichita, Kansas

1-14-1980

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- RANNEY #2
Located: C 1 1 1, Section 7-21-6, Rice County, Kansas

OWNER: F. G. Noll
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMPLETION: October 21, 1979
DATE LOGGED: October 27, 1979

TOTAL DEPTH: 3555'

LOG	DESCRIPTION
0 - 40	Sand
40 - 214	Sand and Shale
214 - 1325	Shale
1325 - 2358	Shale and Lime
2358 - 2725	Lime
2725 - 3010	Shale and Lime
3010 - 3395	Lime
3395 - 3455	Lime and shale
3455 - 3555	Lime, Shale and Cong.

CASING RECORD

Ran 5 joints 8 5/8", 8rd, 20#, Egs. 3,
new casing - 200.66' set @ 209' D.B.
with 190 sacks HA 5. Plug down 4:05
PM, 10-22-70 by Howco.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 2 1979

CONSERVATION DIVISION
Wichita, Kansas

Ran 112 joints, 4 1/2", 8rd, 9.5#,
Egs. 2, used casing - 3595.57' set
@ 355h with 75 sacks salt saturated
cement. Plug down 8:30 AM, 10-27-70.