

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Rice County. Sec. 7 Twp. 21 Rge. (E) 6 (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE  
Lease Owner G. W. Keyes et al  
Lease Name Ramsey Well No. 1  
Office Address Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-30 1949  
Application for plugging filed 11-30 1949  
Application for plugging approved 11-30 1949  
Plugging commenced 11-30 1949  
Plugging completed 11-30 1949  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Ruell Durkee  
Producing formation none Depth to top Bottom Total Depth of Well 3542 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe		0	172	8 5/8"	172	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bridged hole with rock from 3542 to 3540. Mudded hole with heavy mud to 160';  
Set rock bridge at 160' and cement with 15 sacks cement; mudded hole to within  
23' of top; cemented with ten sacks cement, cement returning to base of cellar.


INDEX  
DEC 17 1949 12-17-1949

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to G. W. Keyes Drilling Co.  
Address Box 92 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
I, G. W. Keyes, Part Owner (and) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God  
(Signature) G. W. Keyes  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of December, 1949  
George A. Meyer Notary Public

My commission expires Feb. 10, 1951



WELL LOG

G. W. KEYES et al, OWNERS - RAMSEY # 1  
 SW 1/4 SW 1/4 NE 1/4 Section 7, Township 21, Range 6-W  
 Barton County, Kansas  
 Rice

Elevation : 1692 DF

Figures indicate bottom of formation  
 0 to 60 sand and clay

Pipe Record:

8 5/8" set at 172'

Tops corrected 2' to derrick floor

Heebner shale 2767  
 Base Oread 2789  
 Brown lime 2972  
 Lansing 2992  
 Chert conglomerate 3507  
 Weathered Mississippi 3514

120 sand and shale  
 145 red bed and shale  
 455 shale and shells  
 485 anhydrite  
 750 shale and shells  
 1025 salt and shale  
 1190 shale and shells  
 1450 lime and shale  
 1475 sand  
 1775 shale and lime  
 2215 shale and shells  
 2380 shale and lime  
 2470 shale and shells  
 2530 shale and ~~lime~~ lime  
 2770 lime  
 2775 shale  
 2970 shale and lime  
 3035 lime and shale  
 3195 lime  
 3260 lime and shale  
 3340 ~~lime~~ shale  
 3495 shale and lime  
 3509 shale  
 3516 cherty conglomerate  
 3524 conglomerate ~~and chert~~  
 3542 conglomerate and chert  
 3542 Total Depth D & A

Rotary Commenced 11-19-49  
 completed 11-30-49

STATE OF KANSAS )  
 COUNTY OF BARTON ) SS

I, G. W. Keyes, Part Owner of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

G. W. Keyes

Subscribed and Sworn to before me this 17th day of December, 1949.

Georgel Meyer

My commission expired Feb. 10, 1951.

