


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County. Sec. 7 Twp. 21 Rge. 6 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE SE NE

Lease Owner F. G. Holl
Lease Name Ramsey #1 Well No. _____
Office Address Lyons, Kansas 67554
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/18/79 _____ 19____
Plugging completed 1/7/80 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3530
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	213	none
				4 1/2"	3528	2603'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3500' and ran 3 sacks cement. Loaded hole with salt water, shot pipe at 3018', 2800', 2608', pulled 81 joints. Pumped 4 sacks hulls, 20sacks gel, plug and 85 sacks 50-50 pos, 2% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) on (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of Jan., 19 80

Margaret Melcher
Notary Public.

My commission expires _____



RECEIVED
STATE CORPORATION COMMISSION
1-14-1980
JAN 14 1980

CONSERVATION DIVISION
Wichita, Kansas

15.159.20316.0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- RAMSEY #1
Located: NE SE NE, Section 7-218-6W, Rice County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 1, 1970
COMPLETED: July 7, 1970

TOTAL DEPTH: 3530'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 70 Sand and Shale	Ran 5 joints 8 5/8" 20# new seamless casing. 201.76' pipe set @ 213.26' K.B. Cemented with 190 sacks Pozmix #1 with 3% HA5. Plug down 6:30 PM, 7-1-70.
70 - 215 Shale	
215 - 660 Shale and Shells	
660 - 1060 Shale and Shells - Salt	
1060 - 2935 Shale and Lime	
2935 - 3145 Lime	
3145 - 3360 Lime and Shale	
3360 - 3530 Lime	Ran 111 joints 4 1/2" 9.5# new seamless casing. 3543.99' pipe set @ 3528' K.B. Cemented with 75 sacks Pozmix A with 1/4# floseal per sack. Plug down 7:20 AM, by Howco, 7-7-70.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 2 1979

CONSERVATION DIVISION
Wichita, Kansas