


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 7 Twp. 21a. Rge. 6 W (E) (W)
Location as "NE/CNWxSWx" or footage from lines C NE SW
Lease Owner Northridge Oil Co.
Lease Name Drosback Well No. I-B
Office Address P.O. Box 18271 Denver, Colorado 80218
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-17 1970
Application for plugging filed II-2 1972
Application for plugging approved II-3 1972
Plugging commenced II-18 1972
Plugging completed II-20 1972
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3528' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		612'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3528' to 3500'. Dumped 5 bx of cement. Mudded hole to 215'. Made 15' of rock bridge. Dumped 25 bx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 bx of cement, filling to the bottom of the collar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1972

Judy Lamb
Notary Public.

My commission expires January 5, 1974

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
DR. PAUL HURDOK - WICHITA, KANSAS

WELL NO. 15-159-20325-0000

SEC 7 T. 219 N. 6W
COR. APPROX. C NE SW

DATE OF LOGGING: SEP 17, 1970

COUNTY: Rice

LOGGING DEPTH: 3528
DATE: September 17, 1970

KANSAS

10' 1/2" 100% cemented w/225 px cement ELEVATION 1688 KB
 15' 1/2" 100% cemented w/50 px cement PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATION

10'	50
Clay and red bed	120
Red beds	415
Shale	1200
lime and shale	2590
lime	2720
lime and shale	2905
lime	3155
lime and shale	3250
lime	3345
lime and shale	3528
Rotary Total Depth	3528

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 1 1972
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, INC.

Dean Britting

 Dean BRITTING

STATE OF KANSAS }
 COUNTY OF DEWELock } SS:

Subscribed and sworn to before me a Notary Public in and for the county and state this 17th. day of September, 1970



Elsie Willison

 Elsie WILLISON - Notary Public

Commission Expires: June 30, 1974