

See Correction

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21780-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 7-21S-6W  
330 feet from N Section Line, 990 feet from W Section Line  
Lease/Unit Name: RAMSEY Well Number: 1  
County: RICE Total Vertical Depth: 3588 feet

Operator License No.: 31925  
Op Name: QUALITY WELL SERVICE, INC.  
Address: 415 E. MAIN  
STERLING, KS 67579

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 268 175 SX CMT  
Production: Size 5.5 feet: 3588 150 SX CMT \$116,61  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/05/2001 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE Phone: (316) 727-3410

Proposed Plugging Method: Sand to 3350 -5sxs. 35sxs-1100. 35sxs-600. 318-0

Plugging Proposal Received By: JACK LUTHI WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/05/2001 4:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:  
Sanded bottom to 3350-5sxs of common shot 5 1/2" casing off @ 2170'. Pulled to 1100'. Pumped 35sxs, pulled 600', pumped 35sxs and pulled to 318. Circulated cement to surface.

**INVOICED**  
DATE 03-07-2001  
INV. NO. 2001 061434

RECEIVED  
KCC DISTRICT #2  
FEB 09 2001  
WICHITA, KS

Remarks: UNITED #2645 60/40 4%GEL  
Plugged through: CSG

District: 02 Signed Jack R. [Signature]  
(TECHNICIAN)