

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
800 Billing Building
Wichita, Kansas


WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

pd. 5/10/40

Rice County. Sec. 17 Twp. 21 Rge. 7 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE of SE of NE/4
Lease Owner Westgate-Greenland Oil Company
Lease Name Johnson Well No. #2
Office Address 508 Wolcott Bldg., Hutchinson, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Oil Well
Date, well completed 4-26-37 193
Application for plugging filed 10-21-39 193
Application for plugging approved Yes 193
Plugging Commenced 10-22-39 193
Plugging Completed 10-26-39 193
Reason for abandonment of well or producing formation Not producing in paying quantities
If a producing well is abandoned, date of last production 193
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Durkee
Producing formation Chat Depth to top 3394 Bottom 3397 Total Depth of Well 3397 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
<u>Chat</u>	<u>Oil</u>	<u>3394</u>	<u>3397</u>	<u>12$\frac{1}{2}$" O.D.</u> <u>7" O.D.</u>	<u>159'</u> <u>3350</u>	<u>none</u> <u>2422</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented from 3397 to 3330
Mud " 3330 to 150
Cement " 150 to 135
Mud to base of Cellar
9 Sacks cement at base of cellar

pd. 5/10/40

PLUGGING
FILE NO. 17-21-7
BOOK PAGE 77 LINE 21



5-10-1940

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company
Address 508 Wolcott Bldg. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
A. H. Parks (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

A. H. Parks

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of May, 1940

My commission expires June 22, 1941

Walter L. Ely
Notary Public.

WESTGATE-GREENLAND OIL CO.
 Alberta Johnson No. 2.

SEC. 17 T. 21 R. 7W
 SE SE NE

Total Depth. 3397'
 Comm. 3-31-37 Comp. 4-26-37
 Shot or Treated.
 Contractor.
 Issued. 7-31-37

County. Rice



Elevation.

CASING:
 12 1/2" 159'
 7 " 3350'
 5 3/16" liner 59'7"

Production. Pot. 25 B.

Figures Indicate Bottom of Formations.

Rotary	
surface soil, sand	159
red bed, shale	236
shale & shells	696
red bed, shale	800
shale	1015
shale & shells	1150
lime shells, shale	1272
shale hrd, lime	1362
lime & shale breaks	1435
lime	1642
lime shale	1804
lime	1867
lime, shells	20 68
shale & lime	2195
lime	2678
lime & shale	2735
brkn lime, shale	2773
lime	2779
lime hrd	2815
shale, lime	2824
shale & lime shells	2897
shale & shells	2955
lime	2997
lime hrd	3027
lime sft	3054
lime	3049
lime hrd	3127
lime	3162
lime hrd	3181
lime	3223
shale, shells	3275
oil show 3275-3285	
shale & conglomerate	3294
lime	3296
shale	3350
Standard Tools	
lime	3355
chat	3363
shale	3368
lime & dolomite	3372
shale	3380
lime	3381
shale brown	3384
dolomite <i>small amt Cong</i>	3391
conglomerate	3399
dolomite (trace of green shl)	3394
chat	3397
Total Depth.	

Show of gas 3391-3392



PLUGGING	
FILE	SEC. 17 T. 21 R. 7W
BOOK	PAGE 77 LINE 21

a