

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-20,435-0000

LEASE NAME Johnson

WELL NUMBER JE-3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 17 TWP. 21S RGE. 7W (E or (W)

COUNTY Rice

Date Well Completed 7-13-72

Plugging Commenced 6-8-92

Plugging Completed 6-12-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sterling Drilling Company

ADDRESS P.O. Box 129 Sterling, KS. 67579

PHONE#(316) 278-2131 OPERATORS LICENSE NO. 5142

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3427'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	179'	none
				5 1/2"	3411'	1132'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Could not get sand to bottom went in with line bridge @1100' casing parted,
@1131' pulled casing ran tubing in could not get back inside of casing. Pumped
150 sacks of cement 500# hulls there, pulled to 625' pumped 35 sacks, pulled
to 300' tried to circulate to surface, could not shut down till morning came back

(If additional description is necessary, use BACK of this form.)

(on back)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6859 **RECEIVED**
STATE CORPORATION COMMISSION

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Drilling Company **JUN 18 1992**

STATE OF Kansas COUNTY OF Rice, ss. **CONSERVATION DIVISION**
Wichita, Kansas


R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 17 day of June, 19 92

Irene Herzberg
Notary Public

My Commission Expires: 

cement was 500' pumped 200 sacks got circulated pulled tubing, cement was still falling a little topped it back to surface.